

Special Foundation : Cut off Wall Melbourne, Australia



Customer: Golders / Wagstaff Piling

Client: *Melbourne Metropolitan Council*

Length: 825m bentonite/cement cut off wall

Width: 0.5m

Depth: 19m

Soil Conditions: Sand and weak siltstone, high organics and hydrocarbons

Completed: *August 2009*

The Challenge: Ensure stability of slurry in contaminated ground, and ensure quick installation.

Drilling Fluid: **Bentonil® GTC4 & Bentocryl® 86**

